Welcome

Virtual Presentation

Reconstruction and Watermain Replacement Project

Wilfred Avenue and Prospect Avenue

Limits at Prospect Avenue and at Euler Avenue

September 2025

Posted On-Line

Project Information

Reconstruction Project

Wilfred Avenue and Prospect Avenue

Purpose of the Meeting:	To present for public comment and input, the proposed reconstruction details.
Project Description:	The existing storm and sanitary sewers, watermains, service connections, curbs, sidewalk, and the road structure will be replaced.
Project Funding:	This project is funded by the ratepayers of Kitchener.
Construction Schedule:	Construction is anticipated to begin in late April 2026 with paving completed by late October 2025.
Contractor:	TBD
Project Management:	City of Kitchener Development Services Department, Engineering Services Division.
Personnel to Contact:	Should you have any questions or comments about this project and wish to speak with someone personally, you may call: David Phan, C.E.T., 519-783-8498, david.phan@kitchener.ca Diana Lupsa, P.Eng., 519-783-8422, diana.lupsa@kitchener.ca

Project Highlights

Wilfred Avenue and Prospect Avenue

Overview of work:

- Complete reconstruction of Wilfred Avenue (From Highway 8 to Prospect Avenue) – all underground sewer, watermain, and services up to the right-of-way limits, new curb and gutters, sidewalks, and restoration of asphalt roadway. Watermain replacement along Prospect Avenue from Wilfred Avenue to Euler Avenue, including all water service replacements to the right-of-way limits.

Proposed surface changes:

- The City is proposing elements of the Complete Street approach including narrower roadway and curb radii. The roadway asphalt width will be 7.0m on all roadways (Wilfred Avenue) with wider boulevards and opportunities for new tree plantings.
- New curb and gutter and strategically placed catch basins for improved surface runoff conveyance and stormwater drainage
- All existing sidewalks are removed and replaced with new 1.8m wide concrete sidewalks in the similar alignment.
- All existing driveway aprons are replaced with Concrete[1] with gentle driveway inclines (where grading allows)
- Existing tree removals to facilitate construction and infrastructure installations, and new tree plantings.

Low impact development and environmental improvements:

- Installation of oil & grit separator at the intersection of Wilfred Avenue and Prospect Avenue

[1] U*nless the homeowner requests that the original material be reinstated.*

Questions?

Wilfred Avenue and Prospect Avenue

Personnel to Contact:

Should you have any questions or comments about this project and wish to speak with someone personally, you may call:

David Phan, C.E.T.
519-783-8498
david.phan@kitchener.ca

Diana Lupsa, P.Eng.
519-783-8422
diana.lupsa@kitchener.ca