Welcome

Virtual Presentation

Reconstruction Project

Upper Canada Dr., Farrier Dr., and Farrier Pl.

Limits at Upper Canada Drive and at Farrier Place Intersection

September 2025

Posted On-Line

Project Information

Reconstruction Project

Upper Canada Drive, Farrier Drive, and Farrier Place

Purpose of the Meeting:	To present for public comment and input, the proposed reconstruction details.
Project Description:	The existing storm and sanitary sewers, watermains, service connections, curbs, sidewalk, trails, and the road structure will be replaced.
Project Funding:	This project is funded by the ratepayers of Kitchener.
Construction Schedule:	Construction is anticipated to begin in late April 2026 with paving completed by late October 2025.
Contractor:	TBD
Project Management:	City of Kitchener Development Services Department, Engineering Services Division.
Personnel to Contact:	Should you have any questions or comments about this project and wish to speak with someone personally, you may call: David Phan, C.E.T., 519-783-8498, david.phan@kitchener.ca Kevin Mick, P.Eng., 519-783-8470, kevin.mick@kitchener.ca

Project Highlights

Upper Canada Drive, Farrier Drive, and Farrier Place

Overview of work:

- Complete reconstruction of Farrier Drive (from Upper Canada Drive to 50m north of Farrier Place), Farrier Place (from Farrier Drive to end-of-street), Intersection reconstruction at Upper Canada Drive and Farrier Drive, and trail improvements – all underground sewer, watermain, and services up to the right-of-way limits, new curb and gutters, sidewalks, and restoration of asphalt roadway.

Proposed surface changes:

- The City is proposing elements of the Complete Street approach including narrower roadway and curb radii. The roadway asphalt width will be 7.0m on all roadways (Farrier Drive and Farrier Place) with wider boulevards.
- New curb and gutter and strategically placed catch basins for improved surface runoff conveyance and stormwater drainage
- All existing sidewalks are removed and replaced with new 1.5m wide concrete sidewalks in the same alignment.
- All existing driveway aprons are replaced with Concrete[1] with gentle driveway inclines (where grading allows)
- Existing tree removals to facilitate construction and infrastructure installations, and new tree plantings.
- Trail improvement from Farrier Drive to Upper Canada Park Playground

Low impact development and environmental improvements:

- Installation of underground exfiltration system and oil & grit separator on Farrier Place for surface water

[1] U*nless the homeowner requests that the original material be reinstated.*

Questions?

Upper Canada Drive, Farrier Drive, and Farrier Place

Personnel to Contact:

Should you have any questions or comments about this project and wish to speak with someone personally, you may call:

David Phan, C.E.T.
519-783-8498
david.phan@kitchener.ca

Kevin Mick, P.Eng.
519-783-8470
kevin.mick@kitchener.ca